

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2020-21/OW/WORK_INDENT45958


APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/11/2020-21, Date: 05-12-2020

Name of Work:Development of Roads and Drains in ward no 06

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P Hemanth (SOORYA CREATERS)	
				In Figures	In Words
1	114.47	KSRRB 300-1. Earth work excavation by manual means in Ordinary Soil soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications.MORTH chapter 3. No. 143/ Item No. 19.1/ PWD SR 2018-19	Cum	99.21	Rupees Ninety Nine and Twenty One Paise Only
2	61.2	KSRRB M600-3. Construction of Rolled Cement Concrete mix 1:4:8 OPC cement @180kgs, with 25mm and down size graded granite metal coarse aggregate at 0.85cum and fine aggregates @0.57cum base course with coarse and fine aggregate conforming to IS:383, aggregate cement ratio 12:1 and minimum cement content of 180kg/ cum, aggregate gradation to be as per Table 600-4 after blending, mixing in batching plant at optimum moisture content, transporting to site, laying with a paver with electronic sensor, compacting with 8-10 tonnes smooth wheeled vibratory roller to achieve, the designed flexural strength, finishing and curing complete as per specifications - No. 175/ Item No. 22.3/ PWD SR 2018-19	Cum	2596.4	Rupees Two Thousand Five Hundred Ninety Six and Forty Paise Only
3	7.34	KSRRB 5.3-3 Providing and constructing granite / trap / basalt size stone masonry in basement with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing complete as per specifications.KBS 5-1.13 Page No. 25/ Item No. 5.9/ PWD SR 2018-19	Sqm	3600.0	Rupees Three Thousand Six Hundred Only
4	1.22	KSRRB 4-1.7 : : Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 20mm and down size graded granite metal coarse aggregates @0.84cum and fine aggregates @0.56cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1,4.2/P No. 13/ Item No. 4.7/ PWD SR 2018-19	cum	3600.0	Rupees Three Thousand Six Hundred Only
5	12.24	KSRRB 15.1.3: Providing FLush pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 115/ Item No. 15.1/ PWD SR 2018-19	Sqm	160.56	Rupees One Hundred Sixty and Fifty Six Paise Only
6	12.24	Providing precast slab of 250mm thick including cost of all materials, labour, curing,transportation,loading,unloading,etc.,complete as per the direction of engineer in charge- Data rate	Sqm	3600.0	Rupees Three Thousand Six Hundred Only
7	18	KSRRB M400-17: Providing, laying spreading and compacting graded stones aggregate to wet mix macadam specifications including premixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying, in uniform layers with paver in sub base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. MORTH specification NO. 406,P No. 155/ Item No. 20.18/ PWD SR 2018-19	Cum	1440.92	Rupees One Thousand Four Hundred Forty and Ninety Two Paise Only

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of P Hemanth (SOOP. CREATERS)	
				In Figures	In Words
8	40.8	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 for raft foundation, column footing, main and secondary beams. Page No. 18/ Item No. 4.48/ PWD SR 2018-19	Cum	4154.86	Rupees Four Thousand One Hundred Fifty Four and Eighty Six Paise Only
9	408	Vaccum De- writing with vaccum pump and suction mat and compaction with skin flater clubbed with floatiog disc including cost of generator, HOM of machinery Sereed Vibratory Power Floaterblade and diisc etc. with all lead and lift No. 171/ Item No. 22.7/ PWD SR 2018-19	Sqm	51.89	Rupees Fifty One and Eighty Nine Paise Only
10	128	Providing groove cutting for Concrete pavement width of 5mm to 10mm and depth 80mm- 100mm including cost of cutting machine, generator & HOM of machinery, including cost of blade, coolant etc., including cleaning of groove & providing sand and hot bitumen fillars, and filler metal etc., including cost of conveyance of all materials, labour, lead and lift charges and all other incidental charges as per drawing and as per specifications. (Page No 176., I.No.22.8.1 of PWD S.R 2018-19	Rmtr	103.03	Rupees One Hundred Three and Three Paise Only
11	114.47	KSRRB M100-2. Loading and Unloading of stone boulders by manual means complete as per specification MORTH-100/chapter-1 Page No. 136/ Item No. 17.1/ PWD SR 2018-19	Cum	43.5	Rupees Forty Three and Fifty Paise Only


Signature of the Contractor


Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92
31/02